The Town of Lyme is seeking bids for the following:

Job: Baker Hill Road:

Shoulder graveling:

	 To provide equipment and trucking to install 24" shoulders on each side of the road of 34" hard pack. (Town to supply material) 3,075 feet of roadway
	Total tons projected =
	Per ton price = \$
	Estimated total cost of Job: \$
Swee	ping & Tack: approximately 6,850 yds ² – approximately 137 gallons:
Estim	nated total cost
Pavir	ng:
	• Pave a 2" compacted depth top layer of 3/8" topcoat- 3,075 'x 20' wide.
	Total tons projected =
	Per ton price = \$
	Estimated total cost: \$
Job: Base:	River Road South: 10,985'L x 20'W x 2"H of ½" compacted base mix
	Total tons projected =
	Per ton price = \$
	Estimated total cost: \$
Over	lay: 14,819'L x 20'W x 1.5"H of 3/8" compacted topcoat
	Total tons projected =
	Per ton price = \$
	Estimated total cost: \$
Swee	p & Tack: approximately 21,800 yds ² – approximately 440 gallons:
	Estimated total cost

Handwork: - (3) driveways tie-ins- approximately 20 tons, ½ mix

Estimated cost \$

Shoulder graveling:

- To provide equipment and trucking to install 24" shoulders on each side of the road of 34" hard pack. (Town to supply material)
- 14,819' feet of roadway

All proposals must be sealed and delivered to the Lyme Town Offices (1 High Street) no later than 4:00 PM on Wednesday January 29th 2020. Mailing address: PO Box 126 Lyme NH 03768. Contact Steven Williams with questions: 603-795-4042

Bids will be opened at the regularly scheduled Select board's Meeting on Thursday January 30^{th} 2020 at 9:15AM.

The Town reserves the right to accept or reject any or all bids, modify the length of either Road project to meet the total cost to that of available appropriations.